



Module Assembly and Testing (MAT) [WBS1.05] Status

Bradford Benson (he/him)

**CMB-S4 Collaboration Meeting
May 9-13, 2022**




Outline


- Overview of MAT Scope
- Technical Highlights and progress made in the last year
- Plans through mid-FY23

MAT WBS Workflow And Scope

1.04.03
Cryo 100mK
Electronics
1.04.03.01 thru 05



1.03
Detectors
(Detector Wafer)
1.03.02 thru 07




1.05.02
Module Mech.
Structure


**Readout
Detector
Modules**

1.05.03.01
Horn Arrays


1.05.03.02
Coupling Wafers




1.05.04
Module Assembly



1.04.04 & 05
Cold 4K Electronics
Warm Electronics



1.05.06
Test Equipment






1.05.07
Module Testing



1.06 LAT and 1.07 SAT
Integration and Test in US





Overview of Prototype Development: “Flat” Module Concept

- **Module prototype:**
 - Initial development is focused on the design of a “flat” module to facilitate first “string tests” of prototype detectors and readout.
- **Detector Types/Flavors:**
 - Initial focus on developing LAT MF, SAT MF2, LAT LF types, coordinating with Detectors WBS.
- **Approximate Schedule:**
 - **Summer:** Ramp-up three Module testbeds, focusing on dark module tests.
 - **Fall:** Begin optical tests on LAT MF detector type. Transition from dark to optical tests for SAT MF2 during first half of FY23.





Module-Detector Interfaces

- For initial development on each wafer type, significant DRM work has to be done to define interfaces via Interface Control Documents (ICDs), which define (e.g.);
 - Pixel layout and spacing,
 - Bond-pad layout and sizing; wiring routing
 - Detector-coupling wafer interfaces (e.g., posts, glue channels).
- Advanced ICDs exist for LAT MF, SAT MF2 wafer types, e.g., see progress at:
 - [LAT MF: Detector-Module ICD](#) (23 pages!)
 - [L2 Interface Documents Folder](#)



Prototype Horn Arrays

- Currently doing a cryogenic and fit test of the module assembly with a pre-prototype LAT MF horn array with a dummy wafer at FNAL.
- In addition, fabrication has begun on a new vendor on a set of 5x LAT MF prototype horn arrays.
 - This aims to verify overall prototype design, and that vendor can meet horn specifications.
 - If successful, next plan to fab a set of 5x SAT-MF2 horn arrays, aiming to begin in Summer 2022.



LAT MF horn installed in flat-module in FNAL cryostat

Prototype Coupling Wafers

- “Coupling wafers” historically have been fabricated by NIST
 - e.g., for SPTpol, ACTpol, SO
 - Typically consists of 3x wafers: Choke, WIP, Backshort
- Working with NIST to develop design, and demo a couple commercial vendors that can scale-up for CMB-S4 needs.
 - Layout complete for LAT MF coupling wafer set (see Figure)
- Ordered a set of 5x LAT MF coupling wafers from new vendor (SeeQC), which should be ready for Module assembly by August.
 - If vendor meets QA specifications, plan to order a set of 5x SAT-MF2 wafers in late Summer 2022





Figure 43: **Left:** A photonic choke wafer. **Center:** A waveguide interface plate. **Right:** A backshort array.



Example of required coupling wafer dimensions needed per horn / OMT (taken from Det-Module ICD)



Module Testbeds

- Fermilab cryostat
 - Successful operation of MCE crate with 4K SQUID arrays, with SQUID performance matching SLAC.
 - Initial cryogenic cooldowns of flat-module with “dummy” detector wafer.
- UIUC cryostat
 - Successfully demonstrated load curves with 4K SQUID arrays, 100mK readout, test TESs using MCE crate
- SLAC cryostat
 - Successful operation of MCE crate with 4K SQUID arrays.




4K SSA SQUID card from SLAC in FNAL DR

SQUID V-Phi curves from FNAL




UIUC Testbed and Team

Credit: Jeff Filippini




IV Curves & Noise from UIUC



250 kHz Noise Traces at different TES biases



Cryogenic Demonstration of “Flat” Module

- Currently engaging in a series of cryogenic tests to test the flat-module concept with a dummy wafer to measure performance, e.g.,
 - Overall fit and assembly,
 - Survivability of module components on cooldown (e.g., detector wafer cracks, wire-bond breakage)
 - Thermal gradients across module and wafer with different clamping configurations.




Module Test Equipment

- **Beam-mapper:** Building a warm beam-mapper at FNAL to characterize horn arrays.
 - Status: Assembly at FNAL underway, aim to be online later this summer.
- **Cold-load:** Designing a prototype cold-load for characterizing optical efficiency.
 - Status: Prototype assembly at Case currently underway, with cryogenic-tests at WashU later this summer.
- **Window/IR Filter Stack:** Designing a vacuum window and filter-stack for testbeds.
 - Status: Configuration near-final, aiming for prototype by end of Summer 2022.




Notional MAT Dev. & Testing Schedule: Next 6-12 months

- **Today to end of FY22:**
 - Demonstrate “flat-module” concept, and perform initial DRM string test.
 - Install flat-modules at FNAL, UIUC, SLAC, aiming for testing throughput of at least 1x wafer per 2-months per site
 - Demonstrate vendors for horn array and coupling wafer fab for LAT MF.
 - Focus on LAT MF, SAT MF2 dark testing, with sufficient throughput to test ~6x wafers in FY22.
 - Complete prototype SAT MF2 and LAT LF layout.
- **First-half of FY23:**
 - FNAL testbed transitions to optical operation; first adding a cold load, then a window/IR filter stack.
 - Measure optical performance of LAT MF module.
 - Begin, then complete, fabrication of horn array and coupling wafers for SAT MF2.
 - Measure optical performance of SAT MF2 modules.



Saturation power vs bath temperature with G function fitted for detector R13 C7



Extras



Module Assembly and Testing (MAT) Scope

1. Module structure and assembly


- Design “module” that connects Detector, Readout, and Module (DRM) components into one integrated 100mK assembly.
- Assemble and wire bond components into “testable” detector module.

2. Optical coupling


- Design mm-wave coupling to detector wafer, and build mm-wave coupling components (the feedhorns and coupling wafers)

3. Module testing


- Perform optical and dark tests of integrated module to validate performance of detector module.
- ***Deliver 471 science-grade detector modules to LAT and SAT groups***



MAT Design: RF Coupling To Detector Wafer



Cross-section of Feedhorn and Coupling wafer stack



- Mm-wave power coupled to Detector Wafer through an ortho-mode transducer (OMT), effectively an antenna that feeds power to a transition edge sensor (TES) on the detector wafer.
- Power from the sky is coupled to the OMT via an integrated cavity formed by a Horn Array and Interface Wafers.
- Based on heritage design from several previous experiments (e.g., SPTpol, ACTpol, AdvACT, CLASS, SO)

Next Steps Towards CD-1

- **Module prototype:** Design a “flat” module to facilitate first “string tests” of prototype detectors and readout.
- **Interface wafer prototypes:** RFQ to two potential interface vendors to prototype LAT MF and SAT MF2 design.
- **Develop module test sites:** Outfit 4x testbeds with readout and test equipment to characterize and develop integrated detector modules.












Figure 43: **Left:** A photonic choke wafer. **Center:** A waveguide interface plate. **Right:** A backshort array.

Component and QA Steps Before Handoff to MAT being developed



1.03
Detectors (Detector Wafer)
1.03.02 thru 07

QA Steps:

- In-process tests of Tc, profilometry.
- Test Structures, single pixel array and tests
- Wafer visual inspection
- Warm probe of each TES, measuring resistance, and nearest-neighbor shorts

(08/2020 Review Recommendation)

1.05.03.01
Horn Arrays

QA Steps:

- Visual inspection
- Beam maps of subset of pixels and frequencies
- Profile metrology

1.05.03.02
Coupling Wafers
1.05.02
Module Mech. Structure


QA Steps:

- Visual inspection
- Micrometer spot check

1.04.03
Cryo 100mK Electronics
1.04.03.01 thru 05


QA Steps:

- Visual inspection of individual components
- Warm continuity measurements
- Cryogenic testing of integrated unit, continuity of ea. channel



Science Grade Modules handed off to SATs and LATs after testing


MAT Component and QA Steps Before Handoff



1.04.04 & 05
Cold 4K Electronics
Warm Electronics

QA Steps:

- Visual inspection of individual components
- Cryogenic testing of integrated unit, continuity of ea. channel
- Electrical, network, QA tests of fully populated warm boards



1.05.04
Module Assembly

QA Steps:


- Visual inspection
- Warm probe of full assembly, check resistance and shorts to ground.



1.05.05
High-throughput test
cryostats

QA Steps:

- Cryogenic testing (cooldown time, base temp, etc.)
- Tests of wiring
- Test of computer control




1.05.06
Test Equipment


QA Steps:

- Visual inspection
- Test of computer controls, IO, ADC
- Electrical tests


1.05.07
Module Testing



Assembly #1: Feedhorn And Interface Wafers




Align wafers with pin and slot in jig,
then glue around perimeter





see Optical Coupling talk (S. Simon)

Assembly #2: Wirebonding Flex (MF/HF)

- SAT MF density requires bonding inwards, up on top of backshort
- Wirebond aspect ratios are tight for low frequencies, requiring intermediate step
- Area of ongoing R&D, but early tests (right) for all frequencies are promising



| | 20 GHz | 30/40 GHz | 90/150 GHz | 220/270 GHz |
|------------------|--------|-----------|------------|-------------|
| Bond height [um] | 3393 | 2609 | 1175 | 760 |



All step heights successfully bonded with minimum length/height ratios between 0.65 and 0.82

S. Simon

Detector Bondpads